

**15A NCAC 13B .1625 OPERATION PLAN FOR MSWLF FACILITIES**

(a) The owner or operator of a MSWLF unit shall maintain and operate the facility in accordance with the operation plan prepared in accordance with this Rule.

(b) Operation Plan. The owner or operator of a MSWLF unit shall prepare an operation plan for each proposed area of landfill development consistent with the engineering plan submitted in accordance with Rule .1620 of this Section. The operation plan shall be submitted in accordance with Rule .1617 of this Section and shall include the following:

- (1) Operation drawings. Drawings shall be prepared for each proposed area of landfill development. The drawings shall be consistent with the engineering plan and shall illustrate the following:
  - (A) existing conditions, including the known limits of existing disposal areas;
  - (B) progression of construction cells for incremental or modular construction;
  - (C) progression of operation, including initial waste placement, daily operations, transition contours, and final contours;
  - (D) leachate and stormwater controls for active and inactive subcells;
  - (E) special waste handling areas, such as any asbestos disposal area, within the MSWLF unit;
  - (F) buffer zones, noting restricted use;
  - (G) stockpile and borrow operations; and
  - (H) other solid waste activities, such as tire disposal or storage, yard waste storage, white goods storage, and recycling pads.
- (2) Operation report. The report shall provide a narrative discussion of the operation drawings and contain a description of the facility operation that conforms to the requirements of Rule .1626 of this Section.

*History Note: Authority G.S. 130A-294;  
Eff. October 9, 1993;  
Readopted Eff. September 16, 2021.*